GRUHAM'S

GRUHAMS CONSTRUTION

Design · Build · Inspire

Sree Sai Heights, 3rd Floor, Ideal Home Township, Rajarajeshwari Nagar, Bangalore – 560 098

■ +91 7090110006 | ■ info@gruhams.in | ■ www.gruhams.in

CONSTRUCTION PACKAGE SPECIFICATIONS

Transparent Pricing. Premium Quality. Trusted Execution.

PACKAGE OVERVIEW & PRICING (per sqft. of built-up area)

1. DESIGN

Government & Licenses						
Square Feet Price	**Package - 1** **₹ 1,410/-**	**Package – 2** **₹ 1,950/-**	**Package – 3** **₹ 2,310/-**	**Package – 4** **₹ 2,880/-**	**Package - 5** **₹ 3,250/-**	**Package – 6** **Customized Package**
Govt. License Assistance (Plan Sanction, Electricity, Water & Sewer)	✓Included	✓Included	✓Included	✓Included	✓Included	Included
Architectural Design						
Architectural Layout – 2D	✓ Included	✓ Included	✓ Included	✓ Included	✓ Included	✓ Included
Basic Elevation	✓ Included	✓ Included	✓ Included	✓ Included	✓ Included	✓ Included
3D Elevation	✓ Included	✓ Included	✓ Included	✓ Included	✓ Included	✓ Included
Luxury 3D Elevation (All Views)	✓ Included	—	✓ Included	✓ Included	✓ Included	✓ Included
Technical Floor Plan Presentation + Multiple Site Visits	✓ Included	✓ Included	✓ Included	✓ Included	✓ Included	—
Engineering Drawings						
Structural Design	✓ Included	✓ Included	✓ Included	✓ Included	✓ Included	✓ Included
Electrical Drawing	✓ Included	✓ Included	✓ Included	✓ Included	✓ Included	✓ Included
Plumbing Drawing	✓ Included	✓ Included	✓ Included	✓ Included	✓ Included	✓ Included
Furniture Plan	✓ Included	✓ Included	✓ Included	✓ Included	✓ Included	✓ Included

2. CIVIL STRUCTURE

Steel	TATA Tiscon 550SD	TATA Tiscon 550SD	TATA Tiscon 550SD	TATA Tiscon 550SD	TATA Tiscon 550SD	TATA Tiscon 550SD

Blocks	Solid Concrete 1800 kg/m³ | 4.5 N/mm²	Solid Concrete 1800 kg/m³ | 4.5 N/mm²	Solid Concrete 1800 kg/m³ | 4.5 N/mm²	Solid Concrete 1800 kg/m³ | 10 N/mm²	Solid Concrete 1800 kg/m³ | 10 N/mm²	Solid Concrete 1800 kg/m³ | 10 N/mm²
Cement – Block Work	Birla Super 53 OPC	Birla Super 53 OPC	Birla Super 53 OPC	Birla Super 53 OPC	Birla Super 53 OPC	Birla Super 53 OPC
Cement – Plastering	Ultratech PPC	Ultratech PPC	Ultratech PPC	Ultratech PPC	Ultratech PPC	Ultratech PPC
Block Thickness	4" & 6"	4" & 6"	6" Only	6" & 8"	6" & 8"	Custom
RMC Concrete Mix	M25	M25	M25	M30	M30	M25
Clear Ceiling Height	11 ft	10 ft	11 ft	11–12 ft	12–15 ft	Custom
Plinth Height from RL	2 ft	1'6"	2 ft	2–4 ft	2–4 ft	Custom
Architectural Elements	✓ Included	—	✓ Included	✓ Included	✓ Included	Custom
UG Sump Capacity	10,000 L	10,000 L	15,000 L	18,000 L + 19,000 L	18,000 L + 19,000 L	Custom
UG Sump Construction	RCC Wall	8" Blocks	8" Blocks	RCC Wall	RCC Wall	Custom

3. DOORS & WINDOWS (Budget per unit / per sqft.)

Main Door (frame, shutter & hardware)	—	■ 40,000	■ 80,000	■ 120,000	■ 160,000	Custom
Puja Door (frame, shutter & hardware)	—	■ 30,000	■ 60,000	■ 80,000	■ 120,000	Custom
Room Door (frame, shutter & hardware)	—	■ 8,000	■ 15,000	■ 22,000	■ 35,000	Custom
Bathroom Door (frame, shutter & hardware)	—	■ 5,500	■ 8,000	■ 16,000	■ 20,000	Custom
Windows + Grills (per sq.ft.)	—	■ 500	■ 650	■ 850	■ 1,100	Custom
Window Opening %	—	18%	21%	23%	28%	Custom

4. TILES (Budget per sq.ft.)

Living Room	—	■ 80	■ 140	■ 250	■ 650	Custom
Bedroom & Kitchen	—	■ 60	■ 100	■ 140	■ 250	Custom
Bathroom Wall	—	■ 50	■ 70	■ 90	■ 130	Custom
Bathroom Floor	—	■ 50	■ 70	■ 90	■ 130	Custom
Balcony	—	■ 60	■ 90	■ 120	■ 140	Custom
Terrace	—	—	—	■ 50	■ 80	Custom

5. ELECTRICAL

Points per 1,000 sq.ft.	—	■ 35	■ 40	■ 60	Unlimited	Custom
Wiring	—	Finolex	Finolex	Finolex Gold FR	Finolex Gold FR LESS	Custom
Conduits	—	VIP	VIP	VIP	VIP	Custom

Switches & Plates	—	Anchor Roma	Anchor Roma	Legrand Britzy	Legrand Britzy	Custom
DB & MCB	—	Indo Asian / Schneider	Siemens / Schneider	ABB	ABB	Custom
Home Automation	—	—	—	■ 35,000	■ 70,000	Custom

6. KITCHEN

Tile Dadoing (per sq.ft.)	—	■ 40	■ 65	■ 90	■ 120	Custom
Kitchen Sink (budget)	—	■ 6,000	■ 9,000	■ 14,000	■ 25,000	Custom
Kitchen Tap (budget)	—	■ 2,000	■ 4,000	■ 8,000	■ 12,000	Custom
Utility Sink & Tap	—	■ 6,000	■ 8,000	■ 12,000	■ 15,000	Custom
Kitchen Counter Top (per sq.ft.)	—	■ 90	■ 120	■ 200	■ 320	Custom
Hot Water Supply (Kitchen + Utility)	—	—	—	✓ Included	✓ Included	Custom

7. PLUMBING

Internal Plumbing	—	Supreme / Ashirwad	Supreme / Ashirwad	Supreme / Ashirwad	PPR Pipes	Custom
External Plumbing	—	PVC	PVC	PVC	PVC	Custom
Overhead Tank	—	Ashirwad	Sintex Pure	SS Tanks	SS Tanks	Custom
Provision for Heat Pump	—	✓ Yes	✓ Yes	✓ Yes	✓ Yes	Custom
Rainwater Harvesting	—	✓ Yes	✓ Yes	✓ Yes	✓ Yes	Custom
Separate Pipe – Rainwater Washroom Use	—	—	✓ Included	✓ Included	✓ Included	✓ Included
Sanitary Fitting Budget	—	■ 25,000	■ 40,000	■ 70,000	■ 100,000	Custom
Bidet & Jacuzzi Provision	—	—	✓ Included	✓ Included	✓ Included	Custom

8. PAINTING

Interior	—	Tractor Emulsion	Tractor Shine Emulsion	Premium Emulsion	Royal Shine	Custom
Exterior	—	Ace Weatherproof	Apex Weatherproof	Apex Weatherproof	Apex Ultima Weatherproof	Custom
Doors	—	Synthetic Enamel	Synthetic Enamel	Premium Enamel	High-End PU Enamel	Custom
MS Work	—	Synthetic Enamel	Synthetic Enamel	Premium Enamel	High-End PU Enamel	Custom
Exterior Texture	—	—	✓ Included	✓ Included	✓ Included	Custom

9. WARRANTY & AFTER-SALES CARE

Structural Warranty	10 Years	15 Years	15 Years	15 Years	15 Years	As per selection
AMC	1 Year	1 Year	1 Year	1.5 Years	2 Years	Based on materials

TERMS & CONDITIONS

- *Packages are calculated based on the prevailing base price of raw materials. A price tolerance of ±5% is applicable.*
- *Pricing is for a minimum built-up area of 1,000 sq.ft. per floor. Rates assume soil bearing capacity ≥ 180 kN/m² and foundation depth of 5 ft.*
- *Site and road levels are assumed equal; any difference and backfilling shall attract additional cost. Extraordinary excavation (rock/loose soil) will also incur additional charges.*
- *Costs assume that space for a labour shed and material storage is made available on-site. Small-quantity procurement attracts additional charges.*
- *All statutory charges (BBMP, BESCOM, BWSSB — including deposit & bill amounts) and plan sanction charges are the responsibility of the owner.*
- *No. of toilets considered: 2 nos. per 1,000 sq.ft. Kitchen / utility: 1 no. per 1,000 sq.ft.*
- *Any additional or altered work not included in the quote will be executed at listed prices plus applicable service charges.*
- *Age-related cracks are not covered under warranty. Warranty is void if structural alterations are made by third parties.*
- *The Agreement must be signed within 30 days of booking, failing which this quotation shall be treated as null and void.*

Ready to build your dream home? Call us: +91 7090110006 | info@gruhams.in |www.gruhams.in